

Specifications - Floor Lamps

Poly Canyon Village
Cal Poly, San Luis Obispo

Style: Farrington Series Floor Lamp, 58" tall, heavy-duty lamp shall be UL listed, ADA-compliant with a rocker switch, heavy-duty 3-prong SJT power cord, steel Mega-harp universal swivel for shade adjustment and Perma-lock finial to lock shade to lamp.

Finish: Lamp shall have a durable Taupe color powder coat finish on cup, column, and base with Satin Nickel accent rings.

Lamp Shade: Shade dimensions will be 7" x 15" x 11", and shall be UV resistant, washable, stain and crush-resistant.

Compact Fluorescent Spiral Bulb: All floor lamps shall have installed a 23 watt, compact fluorescent screw-in, self-ballasted spiral bulb.

Quantity: 1,250 each, this represents a total of 618 apartments with two floor lamps per apartment and an additional 14 extra lamps.

Delivery:

- 1) Installation shall be completed in two phases during the summer of 2008 and 2009. Actual dates may vary due to project construction completion. Specific delivery dates will be issued 45 calendar days prior to start delivery date.
 - a. **Phase I** will require 726 floor lamps with compact fluorescent spiral bulbs, of those 14 are extra (not to be installed in resident apartments). Installation of assembled floor lamps will be approximately June 2nd - August 30th, 2008. All vendors installing furniture for this project will be working with the buyer of Contract and Procurement Services to secure an actual installation date.
 - b. **Phase II** will require the balance of 524 floor lamps with compact fluorescent spiral bulbs. Installation of assembled floor lamps will be in 2009, in a similar method as mentioned above.
- 2) The vendor is responsible for the assembly, delivery, and set-into place all floor lamps into designated apartments.
- 3) Vendor is responsible for the hiring and on-site supervision of all labor ready persons.
- 4) The vendor is responsible for the removal and disposal of all packaging materials.
 - a. With prior notification, the University will accept and dispose of "flattened" cardboard containers "only". All other packing material, removal and disposal are the responsibility of the vendor.
- 5) Vendor will provide the awarded vendor with written instructions for all set-in place lamp layouts.
- 6) The multi-story apartment complex has elevator access to all floors.
- 7) Upon request, the vendor will be provided specific lamp placement and the housing structure apartment floor plans prior to the commencement of work.